

A Hospital Design Project in Newcastle Leans on GCP waterproofing solutions

The Newcastle hospital project utilises PREPRUFE® 300R and BITUTHENE® 3000 waterproofing



Project Newcastle Hospitals	
Client The Newcastle Upon Tyne Hospital Trust	
Main Contractor Laing O'Rourke	
Consulting Engineer WSP Consulting Engineers	
Architect Anshen & Allen	
GCP Solution PREPRUFE® 300R pre-applied waterproofing, BITUTHENE® waterproofing, HYDRODUCT® drainage	sheets



The Overview

The Project

A £300 million deal transforming health services in Newcastle involved moving all acute healthcare services from the Newcastle General Hospital site to new state-of-the art facilities in the Royal Victoria Infirmary and Freeman hospital, effectively consolidating three sites into two.

The hospital design project involved some refurbishment to existing buildings, in addition to the construction of new commercial buildings.

The scheme comprised a new Cancer and Renal Services Centre built to the rear of the existing Freeman hospital, as well as a new 810 space multi-storey car park. The development of the Royal Victoria Infirmary included a new Clinical Block, Clinical Support Block, a Children's unit, and A&E department.

"The chosen membrane would have to be suitable for application in a confined site, to permanent formwork."



The hospital design specified waterproofing of basement areas to BS 8102 Grade 1 and 3, with membranes suitable for application on basement walls and below grade slabs. The chosen membrane needed to be suitable for application in a confined site, to permanent formwork.

In addition, drainage was required to manage any hydrostatic pressure on the basement walls. The commercial building design was complicated by expansion joints, which are always high-risk areas below ground.

Project Profile



One of the hospital sites was located on a sloping site with a stepped building, which required semi-basement waterproofing of a grade 3 area. The area also contained a retaining wall that supported earth and required waterproofing to the basement walls.

In addition to supplying products, GCP provided a great deal of design and field support that consisted of site visits and on-site support plus technical and CAD service, as the project contained complex detailing and required problem solving at each step.

To meet the requirements of the hospital design, both PREPRUFE®300R and BITUTHENE®3000 were used on the basement walls in the grade 1 (multi storey car park) and grade 3 basements to protect against the effects of gas penetration.

PREPRUFE[®]delivered a pre-applied waterproofing solution, applicable to below slabs and on confined basement walls.

BITUTHENE[®]3000, a self-adhesive waterproofing membrane, was post-applied to areas constructed with removable formwork, followed by GCP HYDRODUCT[®]drainage sheets to protect the membrane.

Blue360[™] Design Advantage: *Your design needs in a single source.*

gcpat.com.au | Australia customer service: 1800 855 525

GCP Applied Technologies Inc., 2325 Lakeview Parkway, Alpharetta, GA 30009, USA

GCP Australia Pty. Ltd., 14 Colebard Street West, Archerfield, Brisbane, Queensland 4108, Australia

This document is only current as of the last updated date stated below and is valid only for use in Australia. It is important that you always refer to the currently available information at the URL below to provide the most current product information at the time of use. Additional literature such as Contractor Manuals, Technical Bulletins, Detail Drawings and detailing recommendations and other relevant documents are also available on www.gcpat.com.au. Information found on other websites must not be relied upon, as they may not be up-to-date or applicable to the conditions in your location and we do not accept any responsibility for their content. If there are any conflicts or if you need more information, please contact GCP Customer Service.